



CORPS FACTS

Pepin Harbor

U.S. ARMY CORPS OF ENGINEERS

BUILDING STRONG®

The Pepin Harbor is located in the city of Pepin, Wis. It is located at Upper Mississippi River mile 767.0 on the left descending bank. The city of Pepin is the non-Federal sponsor for the project and is required to furnish a suitable placement site for any dredged material.

Details

The small boat harbor was completed in September 1965 at a cost of \$138,406. The length of the small boat harbor is 600 feet. The width of the maneuvering channel is 50 feet. Construction included a breakwater to protect the harbor and in August 1972, another breakwater was added. The U.S. Army Corps of Engineers is authorized to maintain the harbor to a depth of 5 feet below the low control pool elevation of 667.0 mean sea level.

Dredging

Since construction, the Pepin Harbor has been dredged twice by the Corps of Engineers with the last event occurring in 1980. The Corps currently does not have any funding to dredge at Pepin Boat Harbor.

For more information, please contact the Corp's channel and harbors section at (651) 290-5150 or visit www.mvp.usace.army.mil



Public Affairs | FS 38 | 2012

U.S. ARMY CORPS OF ENGINEERS – ST. PAUL DISTRICT

180 FIFTH STREET E., STE. 700, ST. PAUL, MN 55101-1678

www.mvp.usace.army.mil