

DN 24-01

DREDGING NOTICE
U.S. ARMY CORPS OF ENGINEERS
ST. PAUL DISTRICT

NOTICE DATE: April 3rd, 2024

DREDGING CATEGORY: Routine

MEETING DATE: If requested

MEETING TIME:

BOAT REQUIREMENT:

MEETING LOCATION:

DREDGE CUT NAME: FCSB Harbor
(Fountain City Service Base)

RIVER MILE: 733.4 – 733.7

HISTORIC DATA

Frequency: NA

Avg. Quantity/Job: NA

Last Date Dredged: NA

Avg. Quantity/Year: NA

SURVEY DATA

Date Surveyed: March 28th, 2024

Water Surface Elevation: 650.8

Low Control Pool Elevation: 650.2

Net Difference: +0.6

5 Day River Forecast: Slight Increase

DREDGING DATA

Recommended Channel Width: NA

Recommended Dredging Depth: 10 feet

Estimated Quantity: 3,936 yd³

Type of Dredge: Government Mechanical

Proposed Dredging Date: April 4th, 2024

Estimated Duration: 8 Dredging Days – due to working close to the sheet pile wall

Justification for Dredging: The area adjacent to the sheet pile wall is too shallow for the floating plant that needs to be moored there.

MATERIAL PLACEMENT DATA

Proposed Placement Site: Fountain City 1

Location: 5A-731.9-LWP

Site Characteristics: This is a historically used upland beneficial use placement site.

If you have any questions concerning this project or request an onsite meeting, please call me at (651) 290-5155.

Dan Cottrell
Dredging Manager

Pool 5A, Fountain City Service
Base (FCSB) Harbor
River Mile: 733.4 - 733.7
Surveyed: March 28th, 2024
Scale: 1" = 100'

▲ SHEET PILING

CUT-1

▲ WG



