

DREDGING NOTICE
U.S. ARMY CORPS OF ENGINEERS
ST. PAUL DISTRICT

NOTICE DATE: August 21 st , 2024	DREDGING CATEGORY: Imminent
MEETING DATE: August 21 st , 2024	MEETING TIME: 2 PM
BOAT REQUIREMENT: NA	MEETING LOCATION: WebEx
<hr/>	
DREDGE CUT NAME: Head of Richmond Island	RIVER MILE: 712.6 – 713.2

HISTORIC DATA

Frequency: First time
Date Last Dredged:

Avg. Quantity/Job:
Avg. Quantity/Year:

SURVEY DATA

Date Surveyed: August 20th, 2024
Water Surface Elevation: 640.4
Low Control Pool Elevation: 638.5
Net Difference: +1.9'
5 Day River Forecast: Slight Decline

DREDGING DATA


Recommended Channel Width: 450 feet
Recommended Dredging Depth: 12 feet
Estimated Quantity: 24,923 yd³
Type of Dredge: Contract Mechanical Plant 1
Proposed Dredging Date: August 21st, 2024
Estimated Duration: 4 – 24 hour + 6 - 12 hour dredging days
Justification for Dredging: The navigation channel is closed the 9.0' on a recommended bend width of 450'.

MATERIAL PLACEMENT DATA

Proposed Placement Site: Trempealeau
Location: 6-714.1-LWP
Site Characteristics: Trempealeau is a historically used permanent upland beneficial use site all material is expected to be removed.

If you have any questions concerning this project, or if you would like to request an on-site meeting, please call me at 651-290-5155.

Dan Cottrell
Dredging Manager



CUT-5

CUT-7

CUT-6

Richmond Island Lt. (712.8)

FIG 4s

WG

