DREDGING NOTICE U.S. ARMY CORPS OF ENGINEERS ST. PAUL DISTRICT

NOTICE DATE: July 10th, 2025 MEETING DATE: If requested BOAT REQUIREMENT:

DREDGE CUT NAME: Gravel Point

HISTORIC DATA

Frequency: 13% Date Last Dredged: July 8th, 2025

SURVEY DATA

Date Surveyed: July 9th, 2025 Water Surface Elevation: 646.8 Low Control Pool Elevation: 644.4 Net Difference: +2.4' 5 Day River Forecast: Steady decline

DREDGING DATA

Recommended Channel Width: 500 feet Recommended Dredging Depth: 12 feet Estimated Quantity: 3,594 yd³ Type of Dredge: Government Mechanical Proposed Dredging Date: July 10th, 2025 Estimated Duration: 3 dredging days

Justification for Dredging: The navigation channel is restricted to 350 feet between the 9.0' contours and closed between the 10.5' contours on a recommended bend width of 500'.

MATERIAL PLACEMENT DATA

Proposed Placement Site: Homer Location: 6-720.5-RMP Site Characteristics: Homer is a historically used upland placement site, all material is expected to be removed.

If you have any questions concerning this project, or if you would like to request an on-site meeting, please call me at 651-350-2564.

Eric Hammer Channel Maintenance Coordinator DREDGING CATEGORY: Imminent MEETING TIME: MEETING LOCATION: RIVER MILE: 721.9 – 722.1

Avg. Quantity/Job: 10,484 yd³ Avg. Quantity/Year: 1,334 yd³

