

DN 25-39

DREDGING NOTICE
U.S. ARMY CORPS OF ENGINEERS
ST. PAUL DISTRICT

NOTICE DATE: Sept 26 th , 2025	DREDGING CATEGORY: Imminent
MEETING DATE: If requested	MEETING TIME:
BOAT REQUIREMENT:	MEETING LOCATION:
DREDGE CUT NAME: Deadman's Slough	RIVER MILE: 686.8 – 687.5

HISTORIC DATA

Frequency: 20%	Avg. Quantity/Job: 26,291 yd ³
Date Last Dredged: October 27 th , 2024	Avg. Quantity/Year: 5,258 yd ³

SURVEY DATA

Date Surveyed: Sept 22nd, 2025
Water Surface Elevation: 630.2
Low Control Pool: 629.7
Net Difference: +0.5
5 Day River Forecast: Holding Steady

DREDGING DATA

Recommended Channel Width: 400 feet
Recommended Dredging Depth: 12 feet
Estimated Quantity: 29,072 yd³
Type of Dredge: Government Mechanical
Proposed Dredging Date: Sept 29th, 2025
Estimated Duration: 20 Dredging Days
Justification for Dredging: Channel is restricted to 275 feet between the 9' contours and 100 feet between the 10.5' foot contours on a recommended bend of 400'.

MATERIAL PLACEMENT DATA

Proposed Placement Site: Brownsville Containment
Location: 8-688.7-RMP
Site Characteristics: This is a historically used beneficial use stockpile site. All material is expected to be removed.

If you have any questions concerning this project or request an on-site meeting, please call me at 651-350-2564.

Eric Hammer
Channel Maintenance Coordinator

Pool 8, Deadman's Slough
River Mile: 686.8 - 687.5
Surveyed: September 22nd, 2025
Scale: 1" = 200'

CUT-1

CUT-2

Horseshoe Island

Coon Slough Head Lt. (687.2)

FI(2)R 5s

VEG



